



ENREGISTRÉ-REGISTERED ISO 9001 & ISO 14001

WARRANTY BULLETIN

WB12-33



DATE: NOVEMBER 2012 SECTION: 18 - Body

EXPIRATION: NOVEMBER 2014

SUBJECT: WHEELCHAIR LIFT SLIDING DOOR HINGE

BOLTS TIGHTENING

APPLICATION

NOTICE TO SERVICE CENTERS

Verify vehicle eligibility by checking warranty bulletin status with **SAP** or **Vehicle Warranty Information** tool found on Prevost–Systems tab of the Volvo Trucks Dealer Portal

Model	VIN	VI.N. SOCIAL PROPERTY OF THE PARTY OF THE PA
X3-45 Coaches Model Year : 2011 - 2012	From 2PCG33494BC73 <u>5043</u> up to 2PCG33491CC73 <u>5132</u> incl.	

This bulletin does not necessarily apply to all the above-mentioned vehicles, some vehicles may have been modified before delivery. The owners of the vehicles affected by this bulletin will be advised by a letter indicating the Vehicle Identification Number (VIN) of each vehicle concerned.


DESCRIPTION

On the vehicles affected by this bulletin, the wheelchair lift sliding door hinge bolts need to be tightened to ensure proper torque is applied.

Procedure should be performed one bolt at a time to preserve door adjustment.



No material is required.



PROCEDURE



DANGER

Park vehicle safely, apply parking brake, stop engine and set battery master switch(es) to the OFF position prior to working on the vehicle.

- 1. One at a time, each bolt should be un-screwed one turn and re-tightened to 43 lb-ft.
- 2. Apply torque seal.



PARTS / WASTE DISPOSAL

Discard waste according to applicable environmental regulations (Municipal/State[Prov.]/ Federal)

WARRANTY

This modification is covered by Prevost's normal warranty. We will reimburse you thirty minutes (30 min) of labor upon receipt of a completed A.F.A. form on which you must specify as per "Warranty Bulletin WB12-33".

OTHER

		
VBC Bulletin	n/a	
Fail Code	25.00	
Defect Code	09	
System Condition	В	
Causal Part	289179	

You wish to stop receiving this letter and would like to be informed by e-mail of our warranty bulletins? Just e-mail us at technicalpublications@volvo.com and type "ADD" in the subject.