

PREVOST

ENREGISTRÉ - REGISTERED
ISO 9001 & ISO 14001

**WARRANTY
BULLETIN**

Wb99-28



DATE : OCTOBER 1999	SECTION : 23 - Accessories
EXPIRATION: OCTOBER 2000	
SUBJECT : REPLACEMENT OF LAVATORY NIGHT LAMP LIGHT BULB	

APPLICATION

Model	VIN
H3-41 & H3-41 Coaches Model Year : 1998 – 2000	From 2PCH3349XW <u>1012285</u> up to 2PCH33496Y <u>1013355</u> incl.

DESCRIPTION

For the above-mentioned vehicles, replacing the lavatory night lamp light bulb with a long lasting light bulb increases the light bulb lifetime expectancy to 15000 hours.

MATERIAL

Part No.	Description	Qty
562276	Light bulb 657, 28 volts	1

Note : Material can be obtained through regular channels.

PROCEDURE

Warning : Park vehicle safely, apply parking brake, stop engine and set battery master switch(es) to the OFF position prior to working on the vehicle.

1. Locate the night lamp. The night lamp is the lamp that remains constantly lit when the engine is running. It is located near the lavatory door frame.
2. Unscrew the lamp and remove the light bulb by pulling it from the socket (figure 1).
3. Insert the new light bulb in the socket.
4. Reinstall the night lamp.




FIGURE 1 : NIGHT LAMP

WARRANTY

This modification is covered by Prévost Car's normal warranty. We will reimburse you the parts and 1/4 hour (0.25) of labor upon receipt of a completed A.F.A. form on which you must specify as per "Warranty Bulletin 99-28".

Parts disposition :

- Discard according to applicable environmental regulations (Municipal/State[Prov.]/ Federal)